

## Test Report

Client

Hauff-Technik GmbH & Co. KG  
Giengener Straße 35  
89428 Syrgenstein - Landshausen

Order no.:

A 9091-2 / 2010

Date of contract : December 8<sup>th</sup>, 2010

Contract : Testing of the water-tightness of the sealing system flange plate with HRD 150-F2-0 in core hole Ø 150 mm

Specimen delivery : Client

Delivery on : March 3<sup>th</sup>, 2011

Test period : March 3<sup>th</sup> - 4<sup>th</sup>, 2011

Augsburg, June 1<sup>st</sup>, 2011  
di

Department Manager



Holger Dietrich



Laboratory Manager




Hendrik Zaus

This Test Report consists of 9 pages.  
It may only be published unabridged.  
The test results relate only on the items tested. The test material is dissipated.

**CONTENTS**

	page
<b>1 General .....</b>	<b>3</b>
<b>2 Test procedure.....</b>	<b>3</b>
2.1 Test preparation (Hauff-Technik GmbH & Co. KG) .....	3
2.2 Test procedure (Kiwa MPA Bautest GmbH) .....	4
<b>3 Test result .....</b>	<b>8</b>
<b>4 Summary .....</b>	<b>9</b>



## 1 General

Kiwa MPA Bautest GmbH was contracted by Hauff-Technik GmbH & Co. KG to evaluate the water tightness of flange plate with ring seal insert for use as house lead-in.

Therefore a prefabricated test setup was delivered by Hauff-Technik GmbH & Co. KG to our test laboratory in Augsburg.

## 2 Test procedure

### 2.1 Test preparation (Hauff-Technik GmbH & Co. KG)

According to the Manufacturer information the test setup was pre-assembled as follows:

On the surface of a test member with the dimensions 500 x 500 x 350 mm with a core hole  $\varnothing$  150 mm a flange plate with ring seal insert HRD 150-2F-0 was fixed according to the installation instruction. Therefore Fischer long shaft fixing SXR 10 x 80 with screw 7 x 87 was used (see Figure 1). The long shaft fixings SXR were tightened with a torque moment of 20 Nm. Afterwards a pressure bell with manometer and pressure regulator was fixed over the flange on the surface of the test member (see Figure 2).






Figure 1: Fischer long shaft fixing SXR with screw (Manufacturer drawing)

## 2.2 Test procedure (Kiwa MPA Bautest GmbH)

The test member delivered by the Manufacturer was a pre-assembled test member with a test setup with pre-assembled manometer and pressure regulator in accordance with section 2.1 (see Figure 2 to Figure 5). A calibration of the manometer and the pressure regulator by Kiwa MPA Bautest GmbH was not carried out.

After consultation with the Manufacturer a tightness test with water filled pressure bell over a period of 24 h with a nominal pressure of 2,5 bar was carried out. The filling of the pressure bell with water was carried out until the water-level reached the inlet and the air bleed valve respectively.






Figure 2: Test setup




Figure 3: Flange plate with inserted HRD 150-2F-0





Figure 4: Flange plate with removed HRD 150-2F-0







Figure 5: Test Setup (Manufacturer drawing)



### 3 Test result

Subsequent in Figure 6 the manometer display at the beginning and at the end of the tightness test is shown.




Figure 6: Tightness test with water filled pressure bell at a nominal pressure of 2,5 bar (above: manometer display at the beginning of the test at 03/03/2011 13:00; below: manometer display at the end of the test at 03/04/2011 13:00)

#### 4 Summary

*During the tightness test of the sealing system flange plate with HRD 150-2F-0 with water filled pressure bell with a nominal pressure of 2,5 bar over a test period of 24 h no defect as a result of water discharge could be detected.*

Augsburg, June 1<sup>st</sup>, 2011

